



1 PLAN DETAIL - AT TILE

2 PLAN DETAIL - AT TIE-BACK

- 1- Terra Cotta Baguette Module
- 2- Aluminum Reinforcement Inner Tube
- 3- Countersunk Screw, Stainless Steel Recommended
- 4- Gasket
- 5- 1/4" Aluminum End Plate
- 6- Bolt, Stainless Steel Recommended
- 7- Optional Insulating Shim
- 8- Continuous Painted Aluminum Carrier Plate
- 9- Painted Aluminum Tie-Back Bracket
- 10- Waterproofing & Sealant at Exterior Applications
- 11- Back-up Wall

Version-5

SYSTEM:

**Baguette**

DETAIL No.

**2**

OPTION.

**C**

**PLAN DETAIL-  
CONNECTION TO BACKUP  
STUD WALL (INT./EXT.)**

Note: This is conceptual detail; project specific details must be reviewed with Shildan



**Shildan, Inc.**

2047 Briggs Road  
Mount Laurel, NJ 08054  
T: (215) 525-4510  
F: (215) 525-4511

©2008 by Shildan, Inc.